

qa-Door Quantities								
Assembly Code	Assembly Description	Count	Door Description	Type	Width	Height	Thickness	Door Type
C1020	Interior Doors	4	Single-Flush	36" x 84"	3' - 0"	7' - 0"	0' - 2"	8

Grand total

qe-Lighting Fixture Quantities													
Assembly Code	Assembly Description	Count	Unit Description	Type	Lamp	Wattage	Lumens	Description	Manufacturer	Model	URL	Comments	
		8	Light2ALN2x4	Light2ALN2x4			2400 lm						
D5020200	Lighting Equipment	4	Lighting-Troffer_Cooper_ArcLine-Metalux_2ALN_T5-T8	Lighting-Troffer_Cooper_ArcLine-Metalux_2ALN_T5-T8	2			ArcLine Troffer - T5 & T8	Cooper Lighting	2ALN	http://www.cooperindustries.com/content/public/en/lighting/products/recessed_linear_lighting/direct_indirect/_284380.ssd.html	2' X 2' and 2' X 4' - 2 T5 & T8 Lamps	

Grand total

qs-Floor Quantities by Assembly					
Assembly Code	Floor Assembly	Area (Defined By Modeler)	Perimeter	Description	Comments
B1010	Concrete tile	469	131.09		

Grand total: 1 469 131.09

qs-Structural Column Schedule							
Assembly Code	Count	Length	Description	Assembly Description	Type	Comments	Base Level
B10	5	8.50		Superstructure	W10X49		Level 1

Grand total: 5

SCHEDULES/QUANTITIES(C)					
Project number	Project Number		104		
	Date	Issue Date			
	Drawn by	Author			
	Checked by	Checker		Scale	

EVANS	HOLLIS RESTROOM
-------	-----------------

Autodesk® Revit®	www.autodesk.com/revit
------------------	------------------------

qm-Specialty Equipment Quantities							
Assembly Code	Assembly Description	Count	Unit Description	Type	Description	Manufacturer	Model
		4	Shelf_Unit_424	48" x 14"			
C1030100	Fabricated Compartments & Cubicles	2	5'4 stall	60" x 96" Clear			
E1020810	Medical Furniture & Equipment	4	Dispenser_Soap_Wall_Mounted_7472	5868-004	Dispenser, Soap, Wall Mounted	Bradley Corporation	6562
E1020810	Medical Furniture & Equipment	4	GP_EnMotion_Towel_Dispenser_7471	6084-014	Dispenser, Paper Towel, Surface Mount	Georgia Pacific	59462 enMotion Touchless (Smoke Grey)
C1030200	Bath & Toilet Accessories	8	mirror_with_frame_739(2)	ADA			

Grand total

qp-Plumbing Fixture Quantities				
Assembly Code	Assembly Description	Count	Unit Description	Type
D2010110	Water Closets - Single	5	Toilet-Commercial-Wall-3D	15" Seat Height
D2010110	Water Closets - Single	2	Floor_mounted_flush-valve_toilet_w_3-piece_grab_bars_4834	17" Seat Height
D2010400	Sinks	8	Sink Vanity-Round	19" x 19"
		2	Bathroom_Partition_6886	Bathroom_Partition_6886
		1	Non-Recessed_14quot_Bowl_Drinking_FountainChillerPurifier_HighLow_ADA_12998	Non-Recessed_14quot_Bowl_Drinking_FountainChillerPurifier_HighLow_ADA_12998
		5	Bathroom_stall_11701	Regular stall
D2010210	Urinals - Single	3	Urinal-3D-JM_1997	Urinal-Wall-3D

Grand total

SCHEDULES/QUANTITIES(C)				
Project number	Project Number		105	
	Date	Issue Date		
	Drawn by	Author		
	Checked by	Checker		Scale

EVANS	HOLLIS RESTROOM
-------	-----------------

Autodesk® Revit®	www.autodesk.com/revit
------------------	------------------------

qs-Wall Quantities by Assembly						
Assembly Code	Assembly Description	Wall Assembly	Calculated To Butt-End Dimensions		Length - Center To Center	Width
			Area	Volume		
B2010	Exterior Walls	Generic - 4"	146.70	53.79	17' - 8 1/2"	0.37
B2010	Exterior Walls	Generic - 4"	146.70	53.79	17' - 8 1/2"	0.37
B2010	Exterior Walls	Generic - 4"	7.15	2.62	1' - 2 1/2"	0.37
B2010	Exterior Walls	Generic - 4"	141.79	51.99	17' - 3 11/32"	0.37
B2010	Exterior Walls	Generic - 4"	142.85	52.38	17' - 2 11/32"	0.37
B2010	Exterior Walls	Generic - 4"	26.39	9.67	3' - 2 1/4"	0.37
B2010	Exterior Walls	Generic - 4"	51.48	18.88	6' - 6 1/16"	0.37
B2010	Exterior Walls	Generic - 4"	27.07	9.93	3' - 3 1/4"	0.37
B2010	Exterior Walls	Generic - 4"	52.85	19.38	6' - 8 1/16"	0.37
B2010	Exterior Walls	Generic - 4"	13.95	5.12	1' - 5 1/2"	0.37
B2010	Exterior Walls	Generic - 4"	45.20	16.57	5' - 3 13/16"	0.37

qs-Wall Quantities by Assembly						
Assembly Code	Assembly Description	Wall Assembly	Calculated To Butt-End Dimensions		Length - Center To Center	Width
			Area	Volume		
B2010	Exterior Walls	Generic - 4"	10.84	3.97	1' - 5 1/2"	0.37
B2010	Exterior Walls	Generic - 6" 2	61.52	32.81	12' - 2 5/32"	0.53
B2010	Exterior Walls	Generic - 6" 2	13.32	7.10	1' - 3 19/32"	0.53
B2010	Exterior Walls	Generic - 6" 2	37.50	19.25	5' - 3 13/16"	0.53
B2010	Exterior Walls	Generic - 6" 2	13.32	7.10	1' - 3 19/32"	0.53
B2010	Exterior Walls	Generic - 6" 2	61.44	32.77	12' - 2 1/32"	0.53
B2010	Exterior Walls	Generic - 6" 2	169.43	90.36	20' - 5 19/32"	0.53
B2010	Exterior Walls	Generic - 6" 2	250.75	133.73	29' - 6"	0.53
B2010	Exterior Walls	Generic - 6" 2	173.97	92.78	20' - 5 19/32"	0.53
Grand total: 20			1594.21	714.00		

Autodesk® Revit®

www.autodesk.com/revit

EVANS

HOLLIS RESTROOM

SCHEDULES/QUANTITIES(C)

Project number

Date

Drawn by

Checked by

Project Number

Issue Date

Author

Checker

106

Scale