

qa-Ceiling Quantities by Type						
Assembly Code	Assembly Description	Area	Perimeter	Type	Description	Height Offset From Level
C3030210	Suspended Ceilings - Acoustical	489.78		2' x 2' ACT System		8' - 0"

Grand total: 3489.78

qa-Door Quantities								
Assembly Code	Assembly Description	Count	Door Description	Type	Width	Height	Thickness	Door Type
C1020	Interior Doors	2	Single-Flush	36" x 84"	3' - 0"	7' - 0"	0' - 2"	8
C1020	Interior Doors	1	Single-Flush	30" x 84"	2' - 6"	7' - 0"	0' - 2"	11

Grand total

qe-Lighting Fixture Quantities												
Assembly Code	Assembly Description	Count	Unit Description	Type	Lamp	Wattage	Lumens	Description	Manufacturer	Model	URL	Comments
D5020210	Lighting - Fluorescent	8	Light-Troffer-Cooper-Metalux	Light-Troffer-Cooper-Metalux	T8,Biax,T5, or U	Varies per type.	1931 lm	Main Troffer Family	Cooper Industries, Inc.	All Troffer models.	http://www.cooperlighting.com/	Load types thru Type Catalog.

Grand total

qs-Structural Column Schedule							
Assembly Code	Count	Length	Description	Assembly Description	Type	Comments	Base Level
B10	5	8.50		Superstructure	W10X49		Level 1

Grand total: 5

SCHEDULES/QUANTITIES(B)				
Project number	Project Number	104		
Date	Issue Date			
Drawn by	Author			
Checked by	Checker	Scale		

EVANS	HOLLIS RESTROOM
-------	-----------------

Autodesk® Revit®	www.autodesk.com/revit
------------------	------------------------

qm-Specialty Equipment Quantities							
Assembly Code	Assembly Description	Count	Unit Description	Type	Description	Manufacturer	Model
C1030100	Fabricated Compartments & Cubicles	2	5'4 stall	60" x 96" Clear			
E1020810	Medical Furniture & Equipment	6	Dispenser_Soap_Wall_Mounted_7472	5868-004	Dispenser, Soap, Wall Mounted	Bradley Corporation	6562
E1020810	Medical Furniture & Equipment	4	GP_EnMotion_Towel_Dispenser_7471	6084-014	Dispenser, Paper Towel, Surface Mount	Georgia Pacific	59462 enMotion Touchless (Smoke Grey)
C1030200	Bath & Toilet Accessories	8	mirror_with_frame_739	ADA			
		6	Bathroom_Vending_Dispenser_516	Bathroom_Vending_Dispenser_516			

Grand total

qp-Plumbing Fixture Quantities				
Assembly Code	Assembly Description	Count	Unit Description	Type
D2010110	Water Closets - Single	6	Toilet-Commercial-Wall-3D	15" Seat Height
D2010110	Water Closets - Single	2	Floor_mounted_flush-valve_toilet_w_3-piece_grab_bars_4834	17" Seat Height
D2010400	Sinks	8	Sink Vanity-Round	19" x 19"
		2	Bathroom_Partition_6886	Bathroom_Partition_6886
		1	Non-Recessed_14quot_Bowl_Drinking_FountainChillerPurifier_HighLow_ADA_12998	Non-Recessed_14quot_Bowl_Drinking_FountainChillerPurifier_HighLow_ADA_12998
		6	Bathroom_stall_11701	Regular stall
D2010210	Urinals - Single	3	Urinal-3D-JM_1997	Urinal-Wall-3D

Grand total

qs-Floor Quantities by Assembly					
Assembly Code	Floor Assembly	Area (Defined By Modeler)	Perimeter	Description	Comments
B1010	Concrete Slab - 6" 2	16	16.30		
	cream	63	0.00		
	Floors 1	105	0.00		
	Floors 2	96	0.00		
	Floors 3	92	0.00		
	Floors 4	81	0.00		
	Floors 5	55	0.00		

Grand total: 750816.30

SCHEDULES/QUANTITIES(B)				
Project number	Project Number		105	
Date	Issue Date			
Drawn by	Author			
Checked by	Checker		Scale	

EVANS	HOLLIS RESTROOM
-------	-----------------

Autodesk® Revit®	www.autodesk.com/revit
------------------	------------------------

qs-Wall Quantities by Assembly						
Assembly Code	Assembly Description	Wall Assembly	Calculated To Butt-End Dimensions		Length - Center To Center	Width
			Area	Volume		
B2010	Exterior Walls	Generic - 4"	169.43	62.13	20' - 5 19/32"	0.37
B2010	Exterior Walls	Generic - 4"	147.05	53.92	17' - 4 19/32"	0.37
B2010	Exterior Walls	Generic - 4"	39.10	14.34	4' - 11 19/32"	0.37
B2010	Exterior Walls	Generic - 4"	34.00	12.47	4' - 1"	0.37
B2010	Exterior Walls	Generic - 4"	124.38	45.61	14' - 8 19/32"	0.37
B2010	Exterior Walls	Generic - 4"	2.27	0.83	0' - 9 19/32"	0.37
B2010	Exterior Walls	Generic - 4"	125.80	46.13	14' - 8 19/32"	0.37
B2010	Exterior Walls	Generic - 4"	124.38	45.61	14' - 8 19/32"	0.37
B2010	Exterior Walls	Generic - 4"	2.27	0.83	0' - 9 19/32"	0.37
B2010	Exterior Walls	Generic - 4"	121.27	44.46	14' - 8 19/32"	0.37
B2010	Exterior Walls	Generic - 4"	30.46	11.17	3' - 7"	0.37

qs-Wall Quantities by Assembly						
Assembly Code	Assembly Description	Wall Assembly	Calculated To Butt-End Dimensions		Length - Center To Center	Width
			Area	Volume		
B2010	Exterior Walls	Generic - 4"	41.93	15.38	5' - 4 19/32"	0.37
B2010	Exterior Walls	Generic - 6" 2	80.18	42.76	9' - 3"	0.53
B2010	Exterior Walls	Generic - 6" 2	15.58	8.31	1' - 3 19/32"	0.53
B2010	Exterior Walls	Generic - 6" 2	36.22	19.32	4' - 10 19/32"	0.53
B2010	Exterior Walls	Generic - 6" 2	11.05	5.89	1' - 3 19/32"	0.53
B2010	Exterior Walls	Generic - 6" 2	39.42	21.02	9' - 2"	0.53
B2010	Exterior Walls	Generic - 6" 2	48.17	25.69	5' - 9"	0.53
B2010	Exterior Walls	Generic - 6" 2	171.98	91.72	20' - 5"	0.53
B2010	Exterior Walls	Generic - 6" 2	52.70	28.11	5' - 9"	0.53
B2010	Exterior Walls	Generic - 6" 2	106.50	56.80	15' - 6 13/32"	0.53
Grand total: 21			1524.14	652.49		

Autodesk® Revit®

www.autodesk.com/revit

EVANS

HOLLIS RESTROOM

SCHEDULES/QUANTITIES(B)					
Project number	106				
Date					
Drawn by					
Checked by					
					Scale